

1. REFER TO SHEET 0N.1 FOR GENERAL NOTES.
2. REFER TO SELECTION SHEETS FOR FLOORING MATERIAL PRIOR TO CONSTRUCTING STAIRS TO DETERMINE RISER HEIGHTS.
3. REFER TO SHEETS 3.01 & 3.02 FOR FLOOR SYSTEM INFORMATION.

1	STAIRS TO BE ENCLOSED WITH FULL HEIGHT STUDS @ 16" O.C. AND DRYWALLED ON INTERIOR STAIRWELL ONLY TO BOTTOM OF THE RUN
2	2x4 STUDS HELD 1" FROM FOUNDATION WALL WITH 3-1/2" INSULATION.
3	RE: DETAIL D & E/7.01 FOR BASEMENT STAIR FRAMING DETAILS
4	CATTLE-RAIL AT STAIRS RE: SPECIFICATION MANUAL FOR DETAILS
5	DROP CEILING FOR HVAC (HOLD TO BOTTOM OF ADJACENT STEEL BEAM)
6	RIPPED 1x_ WOOD SILL
7	--
8	UNFINISHED BASEMENT CEILING TO BE COVERED IN 1/2" GYPSUM BOARD (WITH THE EXCEPTION OF THE 80 SQ. FT. AREA). JOINTS DO NOT NEED TO BE TAPED OR MUDDED.
9	--
10	80 SQ. FT. MAX. AREA OF CEILING, COMPLYING WITH EXCEPTIONS 3.1 + 3.2, NOT REQUIRING DRYWALL. PERIMETER EDGE MUST BE FIREBLOCKED TO KEEP SEPARATE FROM THE REST OF THE FLOOR ASSEMBLY.

Space for Architect Seal



Copyright © 2016 | 2025 | The Drees Company. All Rights Reserved.
6860 West Snowville Road, Suite 105, Brecksville, OH 44141-3242
Phone: (440) 717-9670

Sheet
Information

1.02

Lower Level Framing Plan

Elevation "A"